PUDUCHERRY TOURISM DEVELOPMENT CORPORATION LIMITED

(A Government of Puducherry Undertaking)

*****

No.129/PTDC/WS/Chunnambar/2022 Puducherry date: 17.07.2023

SHORT QUOTATION NOTICE

Sealed quotations are invited from the established firms to carryout the following works at Paradise Beach in Chunnambar.

Specifications :

SL No.	Description of work	Indicative specification	Qty. required
1	Temporary Wooden Jetty	Jetty Platform Size : 40 ft x 12 ft Support : 16 ft Palm Tree Pole (8 ft under water using Pile 4 ft under Deck | 4 ft above Deck) 2 Nos. of access gallery Size: 20ft x10ft with sufficient handrails to berth boats.	1 No
2	Temporary Thatched Roof Beach Hut	25 ft x 50 ft	2 Nos.
3	Temporary Thatched Roof Beach Umbrella	Diameter – 8 ft Pole Height – minimum 8 ft above ground | 3 ft below the ground.	10 Nos.
4	Temporary Watch Tower	Height – 21 ft | Length – 8 ft | Width - 8 ft	2 Nos.

- Rates to include all taxes, Labour and other charges.
- Prescribed form available on www.py.gov.in or from PTDC Corporate Office.
- The sealed quotation in a sealed cover with all specifications in prescribed format subscribed as **"Quotation for the Supply and Erection of Beach Amenities"** and addressed to the Managing Director, Puducherry Tourism Development Corporation Ltd., No.2, Lal Bahadur Shastri Street, Puducherry – 605 001 shall be submitted on or before **29.07.2023**. upto 12.30p.m.
- The work should be completed within 25 days time from issue of order and no advance will be paid.
- The undersigned reserves all rights either to accept or reject any or all the quotations without assigning any reason thereof.
- Please address queries by mail to ptdc.corporate@gmail.com
- For site inspections, please contact: 90255 89925 (0413) 2335371

MANAGING DIRECTOR